



**EERC**<sup>SM</sup>

Critical Challenges. **Practical Solutions.**



# **DEVELOPING AND VALIDATING RESERVOIR PRESSURE MANAGEMENT AND PLUME CONTROL STRATEGIES IN THE WILLISTON BASIN THROUGH A BRINE EXTRACTION AND STORAGE TEST (BEST)**

Carbon Capture, Utilization & Storage Conference  
Tysons, Virginia  
June 15, 2016

John A. Hamling  
Principal Engineer

# Disclaimer

This presentation was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government, nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof.

LEGAL NOTICE: This work was prepared by the Energy & Environmental Research Center (EERC), an agency of the University of North Dakota, as an account of work sponsored by the U.S. Department of Energy (DOE) National Energy Technology Laboratory. Because of the research nature of the work performed, neither the EERC nor any of its employees makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement or recommendation by the EERC.

# Thank You Project Partners



GE Global Research



## Acknowledgments

This material is based upon work supported by the U.S. Department of Energy  
National Energy Technology Laboratory under Award No. DE-FE0026160.

# Active Reservoir Management (ARM)

## Why ARM?

- Reduce stress on sealing formation
- Divert pressure from leakage pathways
- Reduced area of review (AOR)
- Improve injectivity

## Why Brine Treatment?

- Alternate source of water
- Reduce disposal volumes
- Salable products for beneficial use





Photo Modified from Lawrence Livermore National Laboratory

<https://str.llnl.gov/Dec10/aines.html>

# Phase 1

- Regional characterization
- Site screening and feasibility study
- Site selection
- Geologic modeling
- Reservoir simulation resulting in ARM schema
- Site infrastructure design and field implementation plan
  - Permitting plan
  - Risk assessment
  - MVA plan
  - Site operations plan
  - Costing analysis
  - Brine treatment technology screening and selection process






# The Williston Basin



| Saline Formation               | CO <sub>2</sub> Storage Volume<br>(billions of tons) |
|--------------------------------|--|
| Basal Cambrian                 | 222–720  |
| Beaverhill Lake Group          | <1–5   |
| Minnelusa (Williston Basin)    | 124–451  |
| Elk Point Group                | 1–12   |
| Dakota                         | 135–438  |
| Maha                           | 21–68  |
| Minnelusa (Powder River Basin) | 10–35  |
| Mission Canyon                 | 65–210   |
| Red River                      | 2–6  |
| Rundle Group                   | 1–8  |
| Viking                         | 20–65  |
| Winterburn Group               | 1–6  |
| Woodbend Group                 | 1–5  |
| <b>Total</b>                   | <b>604–2031</b>                                      |

CO<sub>2</sub> Storage in Saline Formations in the PCOR Partnership Region (in billions of tons of CO<sub>2</sub>) (modified from Glazewski and others, 2015)




# Dakota & Minnelusa Groups


- Regional injection targets (CO<sub>2</sub> and saltwater)
- Demonstrated capacity
- Excellent proxy for CO<sub>2</sub> injection into deep saline formations (DSFs)
  - Distributed well network
  - Open DSF system
  - ARM will influence multiple square miles of formation



## Large Stationary Sources metric tons of CO<sub>2</sub>/year



## Saltwater Disposal Wells By Formation




## Site Location





# Field Implementation Plan (FIP)

- Develop ARM strategies
- Validate performance against forecasts
- ARM economics
- Monitoring techniques
- Brine treatment technology test bed
- Demonstrate ARM implementation and operations



# The Site

Formation

Inyan Kara

Broom Creek

Depth, ft

4927–5359

7248–7630

Thickness, ft




338–475

46–113

Average Thickness, ft

390



76



EERC RK51285.CDR


★ Johnsons Corner Site

# The Design (Balance)



EERC WPS2502.AI

# Geomodeling





**Facies**

- Inyan Kara Sand
- Inyan Kara Silty Sand
- Inyan Kara Shale
- Interburden
- Broom Creek Sand
- Broom Creek Shale
- Amsden Reservoir
- Amsden Nonreservoir


**Porosity, %**

40  
35  
30  
25  
20  
15  
10  
5  
0  
No Data






# Infrastructure



EERC WP52503A.AI





# Well Completions

Inyan Kara


| SYSTEM        | ROCK UNIT |           |              | ROCK COLUMN | MAXIMUM THICKNESS<br>FEET (METERS) |
|---------------|-----------|-----------|--------------|-------------|------------------------------------|
|               | SERIES    | GROUP     | FORMATION    | MEMBER      |                                    |
| CRETACEOUS    | Lower     | DAKOTA    | MOWRY        |             | 300 (91)                           |
|               |           |           | NEWCASTLE    |             | 150 (46)                           |
|               |           |           | SKULL CREEK  |             | 140 (43)                           |
|               |           |           | INYAN KARA   |             | 625 (191)                          |
| JURASSIC      |           |           | SWIFT        |             | 725 (221)                          |
|               |           |           | RIERDON      |             | 100 (30)                           |
|               |           |           | PIPER        | BOWEN       | 625 (191)                          |
|               |           |           |              | PIERCE      |                                    |
|               |           |           |              | KLINE       |                                    |
|               |           |           |              | PICARD      |                                    |
| TRIASSIC      |           |           | SPEARFISH    | SAUDE       | 750 (229)                          |
|               |           |           |              | PINE        |                                    |
|               |           |           | MINNEKAHTA   | RELFIELD    | 70 (21)                            |
|               |           |           | OPECHE       |             | 500 (152)                          |
| PERMIAN       |           |           | BROOM CREEK  |             | 375 (114)                          |
|               |           |           | AMSDEN       |             | 450 (137)                          |
|               |           |           | ALASKA BENCH |             | 270 (82)                           |
| PENNSYLVANIAN |           | MINNELUSA | TYLER        |             |                                    |

Estimated Perforated Intervals

BEST-E1

BEST-I1


Swift



Extraction Well (BEST E-1)

Broom Creek


Amsden




Injection Well (BEST I-1)

Critical Challenges. Practical Solutions.


Pressure (psi) Plume at 2020 (no brine extraction) K Layer: 21




Pressure (psi) Plume at 2020 (with brine extraction) K Layer: 21




Pressure (psi) Change from Brine Extraction K Layer: 21




Salinity (molar) Plume at 2020 (no brine extraction) K Layer: 21



Salinity (molar) Plume after Brine Extraction K Layer: 21



Salinity (molar) Change from Brine Extraction K Layer: 21




# Brine Handling


BEST-E1

EERC RK51314 CDR

SIDE VIEW





TOP VIEW



|  |                                   |
|--|-----------------------------------|
|  | PRODUCED WATER                    |
|  | PRODUCED GAS                      |
|  | PRODUCED FLUIDS/GAS               |
|  | VALVE                             |
|  | SPILL CONTAINMENT / TRUCK LOADING |
|  | LIQUID FLOWMETER                  |
|  | GAS FLOWMETER                     |

BEST-11

EERC RK51316 CDR




|  |                                     |
|--|-------------------------------------|
|  | 4" PRETREATMENT/POSTTREATMENT WATER |
|  | SUMP LINE                           |
|  | SOLIDS DISPOSAL                     |
|  | 4" DISPOSAL FROM EFFLUENT STORAGE   |
|  | 4" EQUALIZER LINE                   |
|  | VALVE                               |
|  | OIL CHECK                           |
|  | LIQUID FLOWMETER                    |

# Brine Treatment Test Bed

- Environmentally enclosed facility
  - 24/7, 365 operational capable
- Tailored brine compositions
  - ~4500–300,000 mg/L TDS
- Tailored rates
  - 5–25 gpm
- 30–60-day extended-duration tests
- Pretreatment provided
- Monitoring
  - Energy, flow rates, pressure, temperature, chemicals, etc.
- Waste management

## Technologies Selected in Phase 2






# MVA Program

## Reservoir Surveillance

- Well evaluation
  - Logging, coring, testing
- Borehole to surface EM
- Active reservoir surveillance
  - Pressure, temperature, flow rates, fluid density
- Tracer survey
- Fluid sampling

## Safety and Performance

- Tank and pipeline monitoring
- Flow and density meters
- Power and chemicals
- Pipeline monitoring
- High-level/low-level shutdown
- Remote sensing



# Risk Assessment


- 58 potential risks
  - Technical
  - Resource availability
  - HSE
  - Site access
  - Management
- Mitigation measures built into design and implementation plan
- MVA and HSE plans



## Ready for Implementation

- ✓ Strong partnerships/extensive experience
- ✓ Site secured
- ✓ Established injectivity/injection history
- ✓ Existing pressure plume/confidence in ability to influence through brine extraction
- ✓ Operational flexibility (four-well design)
- ✓ Brine treatment test bed
- ✓ Commercial-scale test
- ✓ MVA plan (performance and safety)
- ✓ Permitting plan (several in place)
- ✓ Costing
- ✓ Risk assessment

**Developing fundamental data and demonstrating the steps necessary to design and implement ARM for large-scale CCS projects.**





THANK YOU!



GE Global Research



# Contact Information

## Energy & Environmental Research Center

University of North Dakota

15 North 23rd Street, Stop 9018

Grand Forks, ND 58202-9018

**[www.undeerc.org](http://www.undeerc.org)**

701.777.5472 (phone)


701.777.5181 (fax)

**John A. Hamling, Principal Engineer**

[jhamling@undeerc.org](mailto:jhamling@undeerc.org)







# Dynamic Simulation

